

LBS INSTITUTE OF TECHNOLOGY FOR WOMEN, POOJAPPURA
THIRUVANANTHAPURAM
QUOTATION NOTICE

No. H/5289/2024

Dated: 14.11.2025

Quotation Number	H/5289/2024
Due date and time for receipt of quotations	19.11.2025 1 PM
Date and time for opening of quotations	19.11.2025 3 PM
Designation and address of officer to whom the quotation is to be addressed	PRINCIPAL LBSITW, POOJAPPURA, TRIVANDRUM.
Superscription: Quotation for constructing a dispersion trench for the existing septic tank in the Ladies Hostel, Poojappura.	

Sealed quotations are invited by the Principal, LBS Institute of Technology for Women, Poojappura, Thiruvananthapuram, Kerala, Pin-695012, for constructing a dispersion trench for the existing septic tank in the Ladies Hostel, Poojappura as specified in the schedule attached below. The rates quoted should be for executing the repairing work along with materials as specified. The necessary superscription, due date for the receipt of quotations and the name and address of officer to whom the quotation is to be sent are noted above. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the execution of the work should also be mentioned. The prices quoted should be inclusive of materials, labour, conveyance and all taxes/ charges etc.

Special conditions if any or printed on quotation notice will not be applicable to the contract unless they are expressly accepted in writing by the undersigned.

Name of work: Dispersion Trench for the Existing Septic tank					
Sl No:	Specification	Quantity	Rate	Unit	Amount (Rs)
1	Excavating trenches of required width for pipes cables,etc including excavation for soak pits and dressing of sides , rammin of bottom , depth upto 1.5 m, including getting out the excavated soil and then returning the soil as required ,in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming ,watering etc. and disposing of surplus excavated soil as directed within a lead of 50 m. Pipes cables etc. as directed by the engineer in charge.	10.00	714.45	Cu.m	7144.50
2	Providing and filling stone aggregates of nominal size 40 mm as directed by the engineer in charge, rate including cost of materials, labour, conveyance etc.Complete	1.00	14000.00	Cu.m	14000.00
3	Providing and fixing Perforated PVC pipes of 110 mm diameter, rate including cost of materials, labour etc as directed by the engineer in charge	40.00	398.64	m	15945.60
Total					37090.10
Applicable GST extra					
(Rupees Thirty Seven Thousand Ninety Only)					

Strike out whichever is not applicable


I/We agree to carry out the work

1. At estimate rate
2. At -----% below estimate rate
3. At -----% above estimate rate

Copy to:

- 1) College Website
- 2) Notice Board.




PRINCIPAL
 Principal
 LBS Institute of Technology
 For Women
 Thiruvananthapuram