

LBS INSTITUTE OF TECHNOLOGY FOR WOMEN, POOJAPPURA
THIRUVANANTHAPURAM
QUOTATION NOTICE

No. H/5289/LBSITW/2024

Dated: 24/06/2026

Quotation Number	H/5289/LBSITW/2024
Due date and time for receipt of quotations	02/07/2026 1 PM
Date and time for opening of quotations	02/07/2026 3 PM
Designation and address of officer to whom the quotation is to be addressed	PRINCIPAL LBSITW, POOJAPPURA, TRIVANDRUM.
Superscription: Quotation for Providing MS poles near the hostel building in the Ladies Hostel.	

Sealed quotations are invited by the **Principal, LBS Institute of Technology for Women, Poojappura, Thiruvananthapuram, Kerala, Pin-695012**, for Providing MS poles near the hostel building of LBSITW, Poojappura as specified in the schedule attached below. The rates quoted should be for executing the repairing work along with materials as specified. The necessary superscription, due date for the receipt of quotations and the name and address of officer to whom the quotation is to be sent are noted above. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the execution of the work should also be mentioned. The prices quoted should be inclusive of materials, labour, conveyance and all taxes/charges etc.

Special conditions if any or printed on quotation notice will not be applicable to the contract unless they are expressly accepted in writing by the undersigned.

Name of work : Providing MS poles near the hostel building of LBSITW, Poojappura					
SI No	Specification	Unit	Quantity	Rate (Rs)	Amount (Rs)
1	Providing and fixing MS pole comprising a vertical pole of 75mm dia and an inclined arm of 50mm welded to the pole at the required inclination in foundation of size 0.45 x 0.45 x 0.60m with cement concrete 1:1.5:3 using 20mm and downgraded aggregate including cost of excavation, concreting, placing, alignment and positioning of pole in concrete, curing, disposal of surplus earth and all incidental charges complete, rate including the cost of all materials, rent of tools, conveyance, labour charges, fabrication charges, rent of scaffolding units if required, as directed by the Engineer-in-charge etc. complete.	E	5.00	6191.00	30955.00
Total					30955.00
GST @ 18%					5571.90
Total (including GST)					36526.90
Total(Round off)					36527.00
(Rupees Thirty Six Thousand Five hundred Twenty Seven only)					

Strike out whichever is not applicable

I/We agree to carry out the work

1. At estimate rate
2. At -----% below estimate rate
3. At -----% above estimate rate

Copy to:

- 1) College Website
- 2) Notice Board.




PRINCIPAL