

LBS INSTITUTE OF TECHNOLOGY FOR WOMEN, POOJAPPURA
THIRUVANANTHAPURAM
QUOTATION NOTICE

No. P/1100/LBSITW/2026

Dated: 04.06.2026

Quotation Number	P/1100/LBSITW/2026
Date and time of issuing quotation	04.06.2026, 10:00 AM
Due date and time for receipt of quotations	10.06.2026, 2 PM
Date and time for opening of quotations	10.06.2026, 3 PM
Designation and address of officer to whom the quotation is to be addressed	PRINCIPAL LBSITW, POOJAPPURA, TRIVANDRUM.
Superscription: Name of Work: Leak Rectification Works in the Main Building of LBSITW, Poojappura.	

Sealed quotations are invited by the Principal, LBS Institute of Technology for Women, Poojappura, Thiruvananthapuram, Kerala, Pin-695012, for the Leak Rectification Works in the Main Building of LBSITW, Poojappura as specified in the schedule attached below. The rates quoted should be for executing the repairing work along with materials as specified. The necessary superscription, due date for the receipt of quotations and the name and address of officer to whom the quotation is to be sent are noted above. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the execution of the work should also be mentioned. The prices quoted should be inclusive of materials, labour, conveyance and all taxes/ charges etc.

Special conditions if any or printed on quotation notice will not be applicable to the contract unless they are expressly accepted in writing by the undersigned.

Name of Work: Leak Rectification Works in the Main Building of LBSITW.

Sl.No	Specification	Qty.	Rate	Unit	Amount
1	Clearing the site by removing the growth of algae and other small bushes, breaking the existing plastering, cracked portion of the concrete if any, leakage of rainwater pipe if any, concreting with 6mm aggregates along with water proofing compound, plastering with water proofing compound and painting the two short vertical walls of library in the ground floor (over the sunshade at a height of 6m), rate including cost of all materials, labour, conveyance of materials, scaffolding units, rent of the scaffolding units etc complete.	job	LS	1	9000.00
2	Clearing the site by removing the growth of algae and other small bushes, breaking the existing plastering, cracked portion of the concrete if any, leakage of rainwater pipe if any, concreting with 6mm aggregates along with water proofing compound, plastering with water proofing compound over the sunshade of the Room No:219 (at a height of 10m), rate including cost of all materials, labour, conveyance of materials, scaffolding units, rent of the scaffolding units etc complete	job	LS	1	8500.00

3	Chipping the existing plastering in the shade area including conveyance of the materials from sixth floor to the ground floor and risk factor as directed by the Engineer-in-charge	10.00	585	Sq.m	5850.00
4	Providing and laying concreting 1:1.5:3 with cement, fine aggregates and 6mm baby aggregates, rate including cost of materials, labour, conveyance and risk factor as directed by the Engineer-in-charge	0.45	16268.2	Sq.m	7320.69
5	wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile including applying additional coats wherever required to achieve even shade and colour. Two coats	15.00	419.9	Sq.m	6298.50
Total					36969.19
GST@18%					6654.45
Total(including GST)					43623.64
Contingencies if any					3376.36
Grand Total					47000.00
(Rupees FortySeven Thousand only)					

Strike out whichever is not applicable
I/We agree to carry out the work

1. At estimate rate
2. At -----% below estimate rate
3. At -----% above estimate rate

Copy to:

- 1) College Website
- 2) Notice Board.




PRINCIPAL
LBS Institute of Technology
For Women
Thiruvananthapuram